



Sales Quote

Quote Date: 7/14/2015 3:34:27 PM
Quote Number: 0005961-0
Project Title: Frisco Colorado Standby Generator
Prepared for: Alberts Water & Wastewater Specialists

Unit Model	PS130-01	Standby / Prime	Emergency Stationary Standby
kWe Rating	130 kWe	UL 2200 Listed	No
Fuel	Natural Gas [NG]	CSA Approved	No
EPA	Certified	Paint Color	White

Fuel System: Natural Gas

Engine Model: PSI 8.8LTCAC 130kW Standby Power Rating at 1800 RPM
Governor - Electronic Isochronous

Voltage: 480/277V 3 Phase 60 Hz 0.8 PF

Gen Model: Marathon 363CSL1607 12 Lead Wired 480V 3 Phase High Wye 130°C Rise Over 27°C Ambient

Voltage Regulator: Marathon SE350 Automatic Voltage Regulator

Control Panel: Blue Star DGC-2020 Microprocessor Based Gen-Set Controller
Mounted Facing Left from Generator End (Unless Specified Otherwise)
Standard Features: Low Oil Pressure, High Coolant Temp, Overspeed, Overcrank Shutdowns
Emergency Stop Pushbutton, Audible Alarm Buzzer with Silencing Switch
Optional Features Include: Generator Protection (Undervoltage, Overvoltage, Underfrequency, Overfrequency, Overcurrent)

Unit Color: White

Enclosure: Level 2 (Weather Proof Enclosure) Powder Coated 14 Gauge Steel
Punched Intake with Baffle and Punched Exhaust Openings
Pitched Roof for Increased Structural Integrity and Improved Watershed
Lockable Handles Keyed Alike on Hinged Side and Rear Doors
Formed Steel Base with Mounting and Lifting Holes
Includes Vibration Mounts to Isolate Unit from Base Rail

Enclosure Options: 150 MPH Wind Rating Standard for Level 2 Enclosure

Cooling: Unit Mounted Radiator (50°C Ambient)

Oil Drain Extension: Plumbed to Bulkhead Fitting in Base

Mainline Breaker: 200 Amp 3 Pole 600 Volt Breaker Mounted & Wired in a NEMA 1 Enclosure

Jacket Water Heater: Engine Block Heater 1500W 120VAC Rated for 20°F
Heater Installed with Isolation Valves and Wired to Terminal

Air Cleaner: Dry Single Stage

Silencer: Catalyst Mounted to Engine - Provides Silencing Function

Battery: 12 Volt System with Rack and Cables

Battery Charger: 12 Volt 6 Amp Mounted and Wired to Terminal

Factory Test: Standard Commercial Testing Includes:
Verification of Alarm Shutdowns, Voltage Settings, Block Loading to Rated kWe and PF

Owner's Manual: Print Copy (Qty 1)

Warranty: 2 Year / 2000 Hour Limited

Notes:

**Additional Options
(Not Included in Price):**

Unit Price (QTY 1)	\$36,381.00
Freight	Not Included
Installation	Not Included
Startup	Not Included
Sales Tax	To Be Determined

Total Price **\$36,381.00**

Payment Terms: Net 30

Lead Time: 8-10 Weeks (Contingent on component availability)

Terms & Conditions

- This quote is valid for a period of 30 days.
- This proposal is our interpretation of your requirement. It includes only the items listed on this quotation. Should there be other requirements or specifications, we will re-quote accordingly.
- Units are shipped wet to include lube oil and 50/50 water and antifreeze mix unless otherwise noted in this quotation.
- All extended piping, wiring, or other than listed above is performed by "others".
- Seller is not quoting, offloading, job site startup, personnel instructions, field testing, or unit installation.
- Quoted prices include normal factory testing, packaging, and instructional literature.
- It is the purchaser and end user's responsibility to ensure that this equipment is operated in accordance with all applicable local, state, and federal laws and regulations governing the use and operation of this equipment.