



# Sales Quote

**Quote Date:** 7/14/2015 3:38:21 PM  
**Quote Number:** 0005962-0  
**Project Title:** Frisco Colorado Standby Generator  
**Prepared for:** Alberts Water & Wastewater Specialists

<b>Unit Model</b>	<b>PS150-01</b>	<b>Standby / Prime</b>	<b>Emergency Stationary Standby</b>
<b>kWe Rating</b>	<b>150 kWe</b>	<b>UL 2200 Listed</b>	<b>No</b>
<b>Fuel</b>	<b>Natural Gas [NG]</b>	<b>CSA Approved</b>	<b>No</b>
<b>EPA</b>	<b>Certified</b>	<b>Paint Color</b>	<b>White</b>

**Fuel System:** Natural Gas  
**Engine Model:** PSI 8.8LTCAC 150kW Standby Power Rating at 1800 RPM  
 Governor - Electronic Isochronous  
**Voltage:** 480/277V 3 Phase 60 Hz 0.8 PF  
**Gen Model:** Marathon 431CSL6202 12 Lead Wired 480V 3 Phase High Wye 130°C Rise Over 27°C Ambient  
**Voltage Regulator:** Marathon SE350 Automatic Voltage Regulator  
**Control Panel:** Blue Star DGC-2020 Microprocessor Based Gen-Set Controller  
 Mounted Facing Left from Generator End (Unless Specified Otherwise)  
 Standard Features: Low Oil Pressure, High Coolant Temp, Overspeed, Overcrank Shutdowns  
 Emergency Stop Pushbutton, Audible Alarm Buzzer with Silencing Switch  
 Optional Features Include: Generator Protection (Undervoltage, Overvoltage, Underfrequency, Overfrequency, Overcurrent)  
**Unit Color:** White  
**Enclosure:** Level 2 (Weather Proof Enclosure) Powder Coated 14 Gauge Steel  
 Punched Intake with Baffle and Punched Exhaust Openings  
 Pitched Roof for Increased Structural Integrity and Improved Watershed  
 Lockable Handles Keyed Alike on Hinged Side and Rear Doors  
 Formed Steel Base with Mounting and Lifting Holes  
 Includes Vibration Mounts to Isolate Unit from Base Rail  
**Enclosure Options:** 150 MPH Wind Rating Standard for Level 2 Enclosure  
**Cooling:** Unit Mounted Radiator (50°C Ambient)  
**Oil Drain Extension:** Plumbed to Bulkhead Fitting in Base  
**Mainline Breaker:** 225 Amp 3 Pole 600 Volt Breaker Mounted & Wired in a NEMA 1 Enclosure  
**Jacket Water Heater:** Engine Block Heater 1500W 120VAC Rated for -20°F  
 Heater Installed with Isolation Valves and Wired to Terminal  
**Air Cleaner:** Dry Single Stage  
**Silencer:** Catalyst Mounted to Engine - Provides Silencing Function  
**Battery:** 12 Volt System with Rack and Cables  
**Battery Charger:** 12 Volt 6 Amp Mounted and Wired to Terminal  
**Factory Test:** Standard Commercial Testing Includes:  
 Verification of Alarm Shutdowns, Voltage Settings, Block Loading to Rated kWe and PF  
**Owner's Manual:** Print Copy (Qty 1)  
**Warranty:** 2 Year / 2000 Hour Limited

**Notes:**

**Additional Options  
(Not Included in Price):**

---

<b>Unit Price (QTY 1)</b>	<b>\$38,840.00</b>
<b>Freight</b>	<b>Not Included</b>
<b>Installation</b>	<b>Not Included</b>
<b>Startup</b>	<b>Not Included</b>
<b>Sales Tax</b>	<b>To Be Determined</b>

---

**Total Price** **\$38,840.00**

**Payment Terms:** Net 30

**Lead Time:** 8-10 Weeks (Contingent on component availability)

---

**Terms & Conditions**

- This quote is valid for a period of 30 days.
- This proposal is our interpretation of your requirement. It includes only the items listed on this quotation. Should there be other requirements or specifications, we will re-quote accordingly.
- Units are shipped wet to include lube oil and 50/50 water and antifreeze mix unless otherwise noted in this quotation.
- All extended piping, wiring, or other than listed above is performed by "others".
- Seller is not quoting, offloading, job site startup, personnel instructions, field testing, or unit installation.
- Quoted prices include normal factory testing, packaging, and instructional literature.
- It is the purchaser and end user's responsibility to ensure that this equipment is operated in accordance with all applicable local, state, and federal laws and regulations governing the use and operation of this equipment.